

Division 23 | Heating, Ventilation, and Air Conditioning

Section 23 01 00 – Design of HVAC Systems

A. Codes and Standards

1. Codes and Standards: The University of Alabama falls under the jurisdiction of the State of Alabama Division of Construction Management. The codes and standards currently adopted and enforced by the Division of Construction Management as the State Building Code are available at http://dcm.alabama.gov/bldg_code.aspx with permitted exceptions. Note that the body of codes adopted and enforced include standards used as reference standards within the codes listed.
2. Where specific/specialized systems and/or installations are not covered by these standards or referenced codes, designer shall reference and specify adherence to industry standard codes and apply best engineering practices applicable to these specific systems or installations. Designer shall identify codes/standards used for design of these specialized systems on the mechanical drawings.

B. Primary Mechanical Systems

1. Variable Air Volume Air Handling Systems with 4-Pipe Chilled Water Cooling and Hot Water Preheat/Reheat, Connected to Campus Central Hydronic System
 - a. This is the preferred system type for new or fully renovated Campus Buildings where Campus Central Hydronic Hot and Chilled Water System piping is nearby and cost effective to connect to.
2. Variable Air Volume Air Handling Systems with 4-Pipe Chilled Water Cooling and Hot Water Preheat/Reheat, Connected to Facility Specific Chiller and Boiler System
 - a. This is the preferred system type for new or fully renovated buildings that require cooling capacity greater than approximately 35 tons that are neither Campus Buildings nor are cost effective to connect to the Campus Central Hydronic Systems.
3. Packaged Rooftop/Split System DX Systems
 - a. This is the preferred system type for small new or fully renovated buildings that have coarse zoning requirements (small numbers of large spaces) and have an aggregate cooling capacity of less than approximately 35 tons.
 - b. Indirect fired natural gas heat is preferred for packaged rooftop systems.
 - c. Hydronic/domestic hot water heat is preferred for split system DX units. If hot water heat is not available, heat pumps with supplemental electric heat are acceptable.
4. Variable Refrigerant Flow (VRF) Systems
 - a. This is a preferred system type for small new or fully renovated buildings that have fine zoning requirements (large numbers of small spaces) and have an aggregate cooling capacity of less than approximately 35 tons.



- b. This system type may also be considered for renovation work within buildings with limited mechanical space/floor-to-floor heights.
- c. When VRF system is used, provide dedicated outside air system as required to meet ASHRAE Standard 62 ventilation requirements.

C. Auxiliary Systems/System Characteristics

1. Airside Economizers are not required by the State of Alabama Division of Construction Management per adopted exceptions. Where good engineering practice dictates and when feasible, airside economizers may be applied to systems. Coordinate with the UA Mechanical Engineer of Construction Administration and UA Project Manager.
2. Energy Recovery Systems shall be provided on Outside Air/Exhaust Systems as required by the ASHRAE 90.1 Energy Standard, version adopted by the Alabama Division of Construction Management.
3. Provide separate ductless split system DX units or DX computer room units as cooling capacity dictates to condition server rooms. This equipment shall be on standby power.
4. Provide dedicated cooling system in the form of a terminal unit or ductless split system DX unit for all telecom/data rooms. If a terminal unit is used, verify that cooling will be available to terminal unit at all times. Air handler serving terminal unit or DX unit must be on standby power. Provide cooling capacity of 18,000 sensible BTU/Hour for each telecom/data room unless instructed otherwise or when internal loads dictate.
5. Provide dedicated cooling system in the form of a terminal unit or ductless split system DX unit for all elevator equipment rooms. If a terminal unit is used, verify that cooling will be available to terminal unit at all times.

D. Outdoor Air Design Conditions

1. HVAC Winter: 10°F
2. HVAC Summer: 96°F DB / 80°F WB

E. Indoor Design Conditions – Acoustics, Temperature and Humidity

1. HVAC related background noise shall meet the criteria outlined in the 2011 ASHRAE Handbook – HVAC Applications, Chapter 48 “Noise and Vibration Control”, Table 1.
2. Summer (air-conditioning) Design Conditions
 - a. Space Maximum Temperature: 74°F
 - b. Space Maximum Humidity: 50% RH
3. Winter (heating) Design Conditions
 - a. Space Minimum Temperature: 70°F
 - b. Winter humidification is generally not required, except where specifically approved by UA.



4. See UA Energy Policy at <https://uafacilities.ua.edu/energy-management/> to setup controls system operating conditions.
5. Design conditions listed above are for Offices, Classrooms, Conference Rooms and Auxiliary spaces supporting these Occupancies. For spaces such as Laboratories, Clean Rooms, Archive Storage, or other spaces with process or equipment specific requirements, obtain design conditions from specialty consultant and confirm criteria with UA Project Manager.

F. Positive Building Pressure

1. The goal is for all buildings to have a slightly positive static pressure. When designing entire building systems provide for sufficient outside air intake and appropriate controls to maintain the building at a positive 0.02" static pressure at ground/entry level relative to outside air. Review plenum design integrity with architect and structural engineer for sealing and insulation.
2. For small systems and/or where static pressure control is not cost effective, provide system capability for positive pressurization up to 10% of total supply airflow.

G. Design for Future Growth/Spare Capacity

1. Prior to start of design obtain requirements for future growth from UA project manager. If future growth of the facility is expected, either provide supplemental system capacity at initial installation to support facility expansion or provide the ability to add future system capacity to the infrastructure provided at initial installation. Future installation of additional capacity and/or connection of additional load/systems shall not require any significant demolition of building elements or mechanical systems.
2. If no future growth requirements are provided by UA project management, provide a minimum of 10% spare capacity in air handling equipment, duct mains and main piping systems.

H. Design Review of Existing Conditions/Capacities

1. In addition to review of existing design drawings – field verify existing conditions. Do not assume that existing record drawings are complete or accurate, if discrepancies between record drawings and existing conditions are found during design surveys and/or during construction notify the owner immediately.
2. Field verify condition of existing equipment and existence of any previously designed spare capacity prior to design. Do not assume that existing equipment is identical to equipment originally designed. Do not assume that existing equipment is operating at original design capacity.

I. Design Requirements – Maintenance Accessibility

1. Locate equipment requiring maintenance so that it is easily accessible primarily in mechanical rooms. Avoid installations that require the use of lifts or scaffolding, or the removal of other equipment for routine maintenance. Equipment and space layout must include service and maintenance space indicated on the plans including room to pull HVAC coils, heat exchanger tube bundles, and energy transfer wheels. Adjacent pieces of equipment shall be separated by minimum 36".
2. Provide access doors to all maintainable equipment located behind walls or above permanent ceilings.



UA Design & Construction Guidelines

3. Large motors, pumps, etc. (≥ 20 hp) shall have provisions for lifting hoists integral to the room construction. This is especially true for any submersed equipment such as sump pumps.
4. Mechanical Equipment Rooms (MER):
 - b. MER should not be located adjacent to classrooms or offices if possible. In all cases, the designer is to consider the control of heat, vibration, and sound transmission from mechanical rooms including the use of insulation and other construction elements. Mechanical room walls should be designed to meet Sound Transmission Coefficient (STC) 60. Doors should meet STC 45.
 - c. MER must be accessible by a standard stair or elevator. Ship's ladders and steep stairs are not acceptable.
 - d. MER must be well lighted with lighting located in such a manner that equipment may be serviced without requiring additional portable lighting.
 - e. Make provisions for storage of two changes of air filters, lubricants, etc.
5. Provide separate concrete housekeeping pads under each mechanical equipment item.
6. Mechanical Equipment Rooms located on floors that are not slab on grade should be curbed or have condensation/drip pans and have all floor penetrations sleeved to 4" above the floor with appropriate fire stopping to prevent water from dripping through to lower levels. Floors should have sealant or coating to prevent water passage. Coordinate with UA building envelope engineer.
7. Mechanical Equipment Rooms with oil or petroleum storage containers with capacity of 55 gallons or greater will have secondary containment with 110% capacity for each container or provide containment for all containers with a capacity of 110% of the largest single container. Provide means for manual drainage of secondary containment areas using a non-flapper type valve.

J. Cost Estimating/Project Budget

1. Cost Estimating shall be performed as required in the Owner/Designer Agreement.

K. Manufacturers

1. The engineer shall use the manufacturers listed in these design standards to select equipment and develop construction specifications.
2. Other manufacturers may be accepted – provide justification and obtain written approval prior to including alternate manufacturers in design drawings or specifications.
3. Sole source specification of equipment must be accompanied by a sole source justification letter and must be approved by UA.

L. Use of Foreign Materials

1. See UA Form – General Conditions of the Contract, Paragraph 50.
2. All monolithic components (those consisting of a single solid, unbroken piece) such as but not limited to pipe, pipe fittings and structural components composed of carbon steel, cast iron, ductile iron, copper, brass, bronze, stainless steel or aluminum shall be produced in the United States or its territories.



3. All other components used within HVAC systems shall be produced in the United States or its territories unless one of the following conditions apply:
 - a. The component in question is not produced at a location within the United States or its territories.
 - b. Components produced within the United States or its territories are not available at prices competitive with equivalent foreign product.
4. Product data for all components produced outside the United States or its territories to be used in HVAC systems must be submitted a minimum of 10 days prior to bid for approval by responsible design consultant and UA Construction Administration. Submittal information shall include fabrication location and reason for substitution of foreign component (availability, cost). Components that have sub-components of foreign manufacture must also have data submitted for approval and reason for submittal clearly noted. Components provided by approved manufacturers where produced outside the United States or its territories must also follow this submittal procedure.

M. Equipment Provided by Owner

1. Where owner desires to purchase specific equipment due to timing and or cost considerations, designer shall be responsible for providing documentation necessary for purchasing including specifications, drawings and details (as applicable). Designer shall also provide assistance and technical support during the purchasing process as needed.
2. Design must reflect actual equipment purchased by the owner. Include submittal data of actual equipment purchased as part of contract documents.
3. Design documents shall instruct the contractor to manage all aspects of equipment receipt, including coordination with the supplier, unloading, storage/relocation as needed. Provide equipment protection as necessary.

N. Existing Systems

1. To define responsibilities of contractors for work performed on existing systems, designers shall include instructions to bidders similar to the following: Work performed on any existing operational equipment or on systems controlling existing operational equipment shall be coordinated through the project's Field Coordinator. The Field Coordinator will coordinate with any additional UA departments or shops as required. Any existing equipment to be reused or remain operational after completion of the contracted work which must be modified, refurbished, or adjusted to complete the scope of work within the Contract shall be verified and documented to be in complete working order prior to commencement of said work. This documentation shall be copied to the UA Field Coordinator for verification. Any damage or change to the condition or operability of the existing equipment caused by work performed after acceptance of this documentation shall be the responsibility of the contractor to repair or replace.

O. Demolition Requirements

1. To maximum extent feasible, remove abandoned branch piping and ductwork back to risers / mains. Remove abandoned conduit and equipment.
2. The A/E must caution the Contractor that all shutdowns of systems serving occupied spaces outside the area of this project shall be absolutely minimized. This will require that, for example,



branch duct runs shall be capped and sealed at the time of partial duct removal to allow use of the remaining duct system until the new ducts are installed. Temporarily rebalance if pressure relationships are critical. Ducts to be reused cannot be left open.

3. Other systems which are presently operating that are to be abandoned, as well as those previously abandoned should be removed.

P. Bid/Construction Drawing Requirements

1. Prepare the following mechanical drawings (as applicable to the project):
 - a. HVAC Schedule Drawings
 - 1) HVAC schedule drawings shall include design criteria. These criteria should include design outdoor temperatures/humidity. These criteria should also include design indoor temperatures, humidity, indoor background noise and cleanliness for each occupancy classification.
 - 2) HVAC schedule drawings shall include outside air calculations as required by the IMC version adopted by the State of Alabama Division of Construction Management. These outside air calculations shall indicate amount of outside air provided by each air handling system and to each space.
 - 3) HVAC schedule drawings shall include detailed design information for all major mechanical equipment, including performance characteristics, utility connection requirements and accessories.
 - 4) If not located on individual drawing sheets, legends identifying drawing symbols/notation shall be provided on the HVAC schedule drawings.
 - b. Demolition Plans
 - 1) Plans to include phasing notes, where applicable.
 - 2) Plans to identify equipment to be turned over to owner following demolition. Note on plans that owner has first right of refusal in addition to identified items; items that are to be turned over to the owner shall be loaded onto owner provided transport vehicle at the jobsite.
 - c. HVAC Airside (Ductwork and Equipment) Plans
 - 1) Include required equipment maintenance and clearance space on plans as dashed outlines or hatched areas.
 - 2) On the ductwork plans, show locations of duct pressure sensors.
 - 3) On the ductwork plans, show locations of duct smoke detectors.
 - 4) On the ductwork plans, show locations of smoke detectors for automatic smoke damper control.
 - d. HVAC Piping Plans



UA Design & Construction Guidelines

- 1) Include all meter locations.
- e. HVAC Control Plans
 - 1) Include all temperature sensor and control switch locations and relationship to devices controlled.
 - 2) Include all equipment and building level controller locations.
- f. ¼" Scale Combined HVAC/HVAC Piping Mechanical Room Plans
 - 1) Include free space required for maintenance.
- g. HVAC Sections/Elevations
 - 1) Include sections of building showing HVAC systems at locations where HVAC components are layered more than (2) components deep.
 - 2) Include sections of building showing HVAC systems at building locations where ceiling space is limited and/or structure is of unusual construction.
- h. HVAC & HVAC Piping Details
 - 1) Include piping schematic diagrams for hot water, chilled water, and condenser water systems. Include system pressures and flows on schematic diagrams. Indicated system pressures shall include calculated system fill pressure.
- i. HVAC Control Diagrams
 - 1) Include diagrams showing all control I/O devices and locations in schematic format.
 - 2) Include sequences of operation for equipment.
 - 3) Reference locations on Control Plans to locate equipment/controllers.
- j. Temporary Conditioning
 - 1) Include instructions for temporary conditioning in renovation projects where necessary to accomplish the scope of work while other portions of the building remain occupied. Instructions should include acceptable temperature and humidity conditions and any design consideration required for any major systems or components, including power requirements to support existing systems in place such as temporary chillers, boilers, piping, or air-side devices.

Q. A/E and Contractor Closeout Documents

1. See UA Front-End Specification 01700 "Project Closeout".

23 05 13 – Common Motor Requirements for HVAC Equipment

- A. Motors shall be 1750 RPM unless service dictates otherwise.



- B. All motors 5 HP and larger shall be premium efficiency, inverter-ready.
- C. Motors installed in outdoor or damp environments shall be TEFC.
- D. Motors installed within custom built central station air handling units shall be TEFC
- E. Motors serving pumps larger than 5 HP shall be TEFC.

23 05 14 – Variable Frequency Drives for HVAC Equipment

- A. All variable frequency drives to be ABB model ACH580.
- B. For all new and/or totally renovated buildings, specify an extra (spare) drive for each motor HP of drive in project to be delivered to UA.
- C. Drives shall be provided without integral bypasses and disconnects. Disconnect to be installed separate from VFD, adjacent to VFD to facilitate service.
- D. Drives shall be specified with NEMA 1 enclosures for standard indoor service, NEMA 12 enclosures for dusty/dirty indoor environments and NEMA 3R enclosures for outdoor or wet environments. Air filters shall be provided for air intake openings only on NEMA 3R and 12 enclosures.
- E. Variable frequency drives shall be provided with BACnet communication interface for direct connection to Building Automation System.
- F. Variable frequency drives shall be de-rated by 10% when installed in high ambient environments.

23 05 16 – Expansion Fittings and Loops for HVAC Piping

- A. Pipe movement as a result of thermal expansion shall be compensated for through the use of a system of expansion loops and/or bends in conjunction with an anchor/guide system. Packed slip, flexible ball, bellows type and other expansion compensating devices shall not be used unless specifically approved by UA.

23 05 19 – Meters and Gauges for HVAC Piping

A. Thermometers

1. Manufacturers: Subject to compliance with requirements below – at consultant’s discretion.
2. Mercury thermometers are not to be used.
3. Thermometer range guidelines:

UA Design & Construction Guidelines

<u>Service</u>	<u>Range(°F)</u>
Chilled Water	0-120
Condenser Water	0-120
Heating Water	30-240

4. Indoor locations: Digital thermometer, variable angle, electronic with LCD display and solar cell, adjustable angle, separable socket and 3.5" stem. Accuracy to +/- 1 degree F. Basis of Design – Weiss Model DVU35.
5. Outdoor or wet locations: Industrial glass thermometer, variable angle, 9" scale, aluminum case with blue liquid filled tube, separable socket and 3.5" stem. Accuracy within 1% of scale range. Basis of Design – Weiss Model A9VU35.
6. A/E shall edit thermometer ranges to project specific requirements and must show clearly on the drawings or details the locations for all thermometers.

B. Pressure Gauges

1. Manufacturers: Subject to compliance with requirements below – at consultant's discretion.
2. Water and Compressed Air Services: 4 ½" diameter face, sealed glass window, silicone filled for connections within 10 feet of pumps.
3. Steam Service: 4 ½" diameter face, sealed glass window, brass coil siphon tube.
4. Select range for twice normal operating pressure.
5. A/E shall edit gauge ranges to project specific requirements and must show clearly on the drawings or details the locations for all gauges.
6. Include pressure gauges across filter sections on air handlers in addition to sensors for BAS alarms.

C. BTU Meters

1. All buildings served by Central Thermal and sections of buildings occupied by different entities shall be metered separately to allow individual utility billing to each department. This includes hydronic systems serving mechanical equipment for other occupancy zones. Where only a small area of a building is occupied by another group such as a portion of a dorm which is occupied by food service, the small area may be metered separately downstream from the main building meter. Any areas for separate metering shall be evaluated by UA staff. Pipe routing should take this into account to accommodate appropriate metering. Discuss with the UA Project Manager, Campus Development Mechanical Engineer, and Energy Manager during the design phase to determine full scope for each project and applicability of small independently or sub-metered areas on a case-by-case basis.
2. BTU meters shall be connected to the BAS for monitoring and data collection by UA Energy Management.



3. Buildings served with hydronic chilled and/or hot water shall be provided with Onicon System-10 BTU meters with Onicon F-3500 insertion type electromagnetic flow meters and appropriate BACnet communications. Where the required straight runs of pipe are not possible for insertion type meters, Onicon F-3200 series in-line type electromagnetic flow meters may be used with three valve bypass for servicing. Install BTU meters where total building loads can be measured. On Central Thermal hot water system connections, the BTU meter shall be located on the return hot water line to the building side of the heat exchanger (lowest temp location).

23 05 23 – General Duty Valves for HVAC Piping

A. General

1. Provide brass valve tags marked for the service. See pertinent service specification for valve type.
2. Valves to have two year warranty.
3. Strainer blow-down valves shall always be quarter turn types, such as ball valves, so that the mesh gets a sudden flow increase instead of a gradual increase.
4. Valves 4" and larger shall have enclosed worm gear operators with position indicators.
5. Check valves 2" and larger in pump discharge and 3" and larger on water riser shall be non-slam type.
6. Acceptable valve manufacturers shall comply with Foreign Materials section above and applicable laws.

B. Ball Valves

1. Manufacturers: Subject to compliance with requirements below – at consultant's discretion.
2. General Service Usage in Lines 2" and smaller: Full port vented ball, full-line size bronze body with type 316 stainless steel ball, stainless steel stem, PTFE seats and FNPT end connections. Provide insulated handle for chilled water service. Pressure/temperature rating to match service requirements but at a minimum must be rated for 250 psig service at 250 degrees F.
3. Provide isolation ball valves at all equipment including coils, pumps, heat exchangers, steam traps, expansion tanks, and on all main branch take-offs.
4. Direct Buried Service Valves for use in Hydronic Hot Water/Chilled Water Applications, 3" and larger: Steel body reduced port ball valve with stainless steel ball and stem and PTFE+C seal. Angle gear driven and pre-insulated. Basis of Design: Vexve DN 200-800.

C. Butterfly Valves

1. Manufacturers: Subject to compliance with requirements below – at consultant's discretion.



UA Design & Construction Guidelines

2. General Service Usage in Lines 2-1/2" and larger: Lug pattern, ductile iron body with extended neck for 2" minimum insulation. Valve to include molded-in EPDM liner bonded and fused to valve body, aluminum bronze disc and 416SS blowout-proof stem. Pressure/temperature rating to match service requirements but at a minimum must be rated for 150 psig service at 250 degrees F.
3. Do not use butterfly valves in steam service.
4. Sizes 4" and above shall have gear operated chain if located more than 8' above floor. Chain shall reach no lower than 7'-0" of floor or operating platform.

D. Gate Valves

1. Manufacturers: Subject to compliance with requirements below – at consultant's discretion.
2. Steam Service Usage in Lines 2" and smaller: Bronze body with bronze trim, union bonnet, rising stem, handwheel, inside screw with backseating stem, solid wedge disc and FNPT ends. Pressure/temperature rating to match service requirements but at a minimum must be rated for 125 psig saturated steam service.
3. Steam Service Usage in Lines 2-1/2" and larger: Ductile iron body with bronze trim, bolted bonnet, outside screw and yoke, handwheel, solid wedge disc with bronze seat ring and flanged ends. Pressure/temperature rating to match service requirements but at a minimum must be rated for 150 psig saturated steam service.

23 05 29 – Hangers and Supports for HVAC Piping and Equipment

A. Pre-Engineered Support Systems

1. The use of pre-engineered support systems (such as Unistrut or B-Line) for HVAC piping and equipment is preferred as these systems have clearly defined installation instructions, load criteria, and safety factors.

B. Custom/Field Fabricated Support Structures

1. Custom and/or field fabricated support structures for support of or access to HVAC piping and equipment for equipment weighing over 600 lbs and/or piping load density equal to or greater than a single 4" carbon steel pipe per support point shall be detailed and designed by the A/E.

C. Hanger/Support Design Coordination

1. HVAC equipment, HVAC piping 4" or larger and duct weighing more than 20 lbs/linear foot shall be shown on and coordinated with structural drawings.
2. Hangers shall be installed within 12" of any change in direction in addition to other spacing requirements.

D. Support Materials/Details

1. Support materials shall be carbon steel unless noted otherwise.



UA Design & Construction Guidelines

2. Indoor/Dry Environments: Support materials shall be provided with an electroplated zinc coating (0.2 mil coating) or painted with an epoxy based primer. Apply zinc coating or primer to ends of cut supports or areas where coatings have been removed during assembly/construction.
3. Outdoor/Wet Environments: Support materials shall be provided with a thermoset epoxy coating such as Unistrut Perma-Green, constructed of corrosion resistant materials such as stainless steel/aluminum or painted with an outdoor duty epoxy based primer/paint system. Apply coating or primer/paint to ends of cut supports or areas where coatings have been removed during assembly/construction.
4. Where uninsulated piping comes into contact with metal supports or support systems, provide elastomeric cushion or clamp to prevent direct metal to metal contact.

E. Anchoring Systems

1. Overhead equipment, component, and system support must utilize mechanical fasteners for concrete, wood, or metal. Powder driven anchors are not allowed.

23 05 33 – Heat Tracing for HVAC Piping

- A. Manufacturers: Subject to compliance with requirements below – at consultant’s discretion.
- B. Apply heat tracing to all above-grade HVAC hydronic piping exposed to outdoor conditions, including piping in unconditioned attics.
- C. Heat trace shall be applied under pipe jacket and insulation.
- D. Heat trace shall be self-regulating and rated for a minimum of 5W/LF.
- E. All trace shall be thermostatically controlled. This may be accomplished via a central distribution panel or individual controllers for separate pipe sections.
- F. Heat trace shall have LED indicating lights connected to the end of the heat tape to allow visual verification of proper operation

23 05 48 – Vibration and Seismic Controls for HVAC

A. Seismic Controls

1. HVAC equipment, ductwork, piping and other components to be provided with Seismic restraint and control devices as required by ASCE 7-05. Mechanical design engineer to specify seismic controls based upon building Seismic Design Category and HVAC system use/service.

B. Vibration Controls

1. In general, apply vibration control and isolation as recommended in the 2011 ASHRAE Handbook – HVAC Applications, Chapter 48 “Noise and Vibration Controls”. Designer to review with UA during



design process all proposed vibration control methods, strategies and components prior to final selection.

23 05 53 – Identification for HVAC Duct, Piping, and Equipment

A. Duct Labeling

1. Label concealed duct mains and exposed duct mains within mechanical rooms with fluorescent green spray paint stencil every 20 LF and a minimum of once within each room.
2. Letter height to be 2" and label to include directional arrow and duct type information – "Supply", "Return", "Exhaust", "OSA".

B. Pipe Labeling

1. Pipe labels are to comply with ANSI/ASME A13.1 – 1996 for labeling location/frequency, letter height, color field length and directional arrow requirements. Note that hydronic hot water supply and return shall have black on yellow color scheme in lieu of white on green.
2. Pipe labels are to be suitable for both indoor and outdoor use.
3. Pipe labels may be cylindrically coiled or flat strap-around markers with heavy duty nylon ties. Substitute stainless steel bands for nylon ties for outdoor duty applications.
4. Provide unique pipe labeling to distinguish between Central Thermal and Building hot water or chilled water piping.

C. Equipment Labeling

1. All equipment shall be labeled with multilayer, multicolor phenolic plastic labels with data mechanically engraved in the label.
2. All access doors to fire dampers, fire/smoke dampers and grease exhaust cleanout points shall be labeled with multilayer, multicolor phenolic plastic labels with data mechanically engraved in the label.
3. Phenolic plastic labels shall be a minimum of 1/16" thick, with letters a minimum of ¼" in height.
4. Labels shall be mechanically attached to equipment with stainless-steel self-tapping screws where feasible. Contact type permanent adhesive is permitted where mechanical attachment is not feasible.
5. Labels shall have white letters on black background unless equipment is served by emergency power. Equipment served by emergency power shall have white letters on red background.

D. Warning Labels

1. Warning labels shall be provided at locations and/or equipment where specific actions must be performed on a regular basis to avoid compromise of system operation.
2. Provide warning labels at equipment disconnects where equipment is served by a remote VFD.



3. Warning labels shall have white letters on yellow background. See “Equipment Labeling” above for other requirements.

E. Warning Tape for Below Grade Pipe

1. Pipe buried underground shall be provided with warning tape. Warning tape shall be installed continuously along the length of pipe 12 to 18 inches above the pipe, prior to backfilling.

23 05 63 – Anti-Microbial Coatings for HVAC Ducts and Equipment

- A. Anti-microbial coatings for HVAC ducts and equipment are generally not required. Contact UA project manager if coatings are recommended for project specific application.

23 05 66 – Anti-Microbial Ultraviolet Emitters for HVAC Ducts and Equipment

- A. Anti-microbial ultraviolet emitters for HVAC ducts and equipment are generally not required. Contact UA project manager if emitters are recommended for project specific application.

23 05 93 – Testing, Adjusting, and Balancing for HVAC

- A. Testing, Adjusting and Balancing of HVAC systems to be performed by a NEBB, AABC, or TEB certified testing firm.
- B. Testing firm shall have documented prior TAB experience on the UA campus. If firm does not have prior experience with work on UA campus, firm must submit qualifications to UA prior to bid for approval.
- C. TAB report shall include entering and leaving dry bulb and wet bulb temperatures of heating and cooling coils taken at the time of testing and balancing as well as outdoor dry bulb and wet bulb temperatures.
- D. All temperature and airflow readings shall be as tested and measured not data copied from the BAS.
- E. Startup and operation of air handling equipment should not commence until sanding of sheetrock, cutting, grinding of floors, and other dust producing tasks are complete. Minimum MERV 8 pleated filter media should be installed on all grilles and diffusers to protect duct openings from dust during the course of construction. Ductless fan coil units should be protected from dust with additional MERV 8 pleated filter media or adhesive plastic film on the face. Filters in units and at grilles shall be changed regularly throughout construction to maintain cleanliness of duct and air handlers.
- F. Test and record flows at all VAV terminal unit reheat coils.

23 07 13 – HVAC Duct Insulation



UA Design & Construction Guidelines

- A. Manufacturers: At consultant's discretion.
- B. Provide duct insulation thickness and thermal conductivity in conformance with the edition of ASHRAE 90.1 currently adopted and enforced by the State of Alabama Division of Construction Management.
- C. Provide insulation and associated accessories with flame-spread index of 25 or less, and smoke developed index of 50 or less, as tested by ASTM E 84 (NFPA 255) method.
- D. Use of mechanical fasteners and tape to secure insulation is not acceptable unless augmented by a sealant/adhesive system such as mastic.
- E. Supply Duct
 - 1. Concealed Applications: Wrap with glass fiber external duct wrap.
 - 2. Interior Exposed Applications: Line with glass fiber duct liner or provide double wall insulated duct.
 - 3. Exterior Applications: Exterior duct systems are to be determined through discussions with the UA Project Manager and UA Campus Development Mechanical Engineer based on specific project requirements.
- F. Return Duct and Transfer Duct:
 - 1. Interior Applications: Line with glass fiber duct liner for sound attenuation purposes.
 - 2. Exterior Applications: Exterior duct systems are to be determined through discussions with the UA Project Manager and UA Campus Development Mechanical Engineer based on specific project requirements.
- G. General Exhaust Duct: Line with glass fiber duct liner only as required for sound attenuation purposes. Wrap with glass fiber external duct wrap downstream of fans to building exit point.
- H. Grease Exhaust Duct: Wrap with commercial kitchen grease duct enclosure system in compliance with ASTM E2336 from hood connection to building exit point.
- I. Outside Air Duct
 - 1. Concealed Applications: Wrap with glass fiber external duct wrap.
 - 2. Interior Exposed Applications: Provide double wall insulated duct.
 - 3. Interior Exposed Applications (Mechanical Rooms): Wrap with glass fiber external duct wrap.
 - 4. Exterior Applications: Exterior duct systems are to be determined through discussions with the UA Project Manager and UA Campus Development Mechanical Engineer based on specific project requirements.



23 07 16 HVAC Equipment Insulation

- A. Manufacturers: At consultant's discretion.
- B. Hot Equipment: Glass Fiber Insulation – provide removable covers for equipment access points.
- C. Cold Equipment: Foamed Plastic Insulation – provide removable covers for equipment access points.
- D. Chilled water shall not be circulated through the piping system until all piping, pumps, valves, hydronic accessories, etc. have been fully insulated, inspected/observed, and approved to proceed with chilled water production and circulation. This should be clearly stated for the bidders and included in the project's construction Contract Documents.

23 07 19 HVAC Piping Insulation

- A. Manufacturers: At consultant's discretion.
- B. Provide piping insulation thickness and thermal conductivity in conformance with the edition of ASHRAE 90.1 currently adopted and enforced by the State of Alabama Division of Construction Management.
- C. Provide insulation and associated accessories with flame-spread index of 25 or less, and smoke developed index of 50 or less, as tested by ASTM E 84 (NFPA 255) method.
- D. Use of mechanical fasteners and tape to secure insulation is not acceptable unless augmented by a sealant/adhesive system such as mastic.
- E. Provide a continuous, unbroken, vapor seal on all cold pipe surfaces. Guides and anchors secured directly to cold surfaces shall be adequately insulated and vapor sealed to prevent condensation.
- F. Provide insulation protection shields fabricated from galvanized steel at all pipe hangers in accordance with MSS SP-69.
- G. Insulation shall be installed continuous through supports and wall penetrations. In addition to hydronic and steam piping, this shall also apply to condensate drains and refrigerant piping where saddles and clamps shall be installed on the outside of insulation including at strut support interior and exterior across concrete pads.
- H. Foamed plastic insulation at elbows shall be mitered.
- I. Chilled water shall not be circulated through the piping system until all piping, pumps, valves, hydronic accessories, etc. have been fully insulated, inspected/observed, and approved to proceed with chilled water production and circulation. This should be clearly stated for the bidders and included in the project's construction Contract Documents.

J. Chilled Water Supply and Return

1. Concealed Applications: Cellular Glass or Polyisocyanurate (Trymer) Pipe Insulation with factory applied jacket.
2. Interior Exposed Applications: Cellular Glass or Polyisocyanurate (Trymer) Pipe Insulation with PVC jacket. PVC jacket is required in boiler rooms, pump rooms, and large air handler rooms only. Consult UA Project Manager and/or Campus Development Mechanical Engineer.
3. Interior Exposed Applications (Mechanical Rooms): Cellular Glass or Polyisocyanurate (Trymer) Insulation with aluminum jacket up to 8' above floor, factory applied jacket elsewhere.
4. Exterior Applications: Cellular Glass or Polyisocyanurate (Trymer) Pipe Insulation with Aluminum Jacket and Heat Trace.

K. Hydronic Hot Water Supply and Return

1. Concealed Applications: Glass Fiber Pipe Insulation with ASJ.
2. Interior Exposed Applications: Glass Fiber Pipe Insulation with PVC jacket. PVC jacket is required in boiler rooms, pump rooms, and large air handler rooms only. Consult UA Project Manager and/or Campus Development Mechanical Engineer.
3. Interior Exposed Applications (Mechanical Rooms): Glass Fiber Pipe Insulation with ASJ.
4. Exterior Applications: Cellular Glass Pipe Insulation with Aluminum Jacket and Heat Trace.

L. Refrigerant Piping

1. Concealed Applications: Foamed Plastic Insulation.
2. Interior Exposed Applications: Foamed Plastic Insulation with PVC jacket. PVC jacket is required in boiler rooms, pump rooms, and large air handler rooms only. Consult UA Project Manager and/or Campus Development Mechanical Engineer.
3. Interior Exposed Applications (Mechanical Rooms): Foamed Plastic Insulation.
4. Exterior Applications: Foamed Plastic Insulation with Aluminum Jacket.

M. AC Unit Drain Lines

1. Concealed Applications: Foamed Plastic Insulation.
2. Interior Exposed Applications: Foamed Plastic Insulation with PVC jacket. PVC jacket is required in boiler rooms, pump rooms, and large air handler rooms only. Consult UA Project Manager and/or Campus Development Mechanical Engineer.
3. Interior Exposed Applications (Mechanical Rooms): Foamed Plastic Insulation.



N. Steam and Steam Condensate Piping

1. Concealed Applications: Glass Fiber Pipe Insulation.
2. Interior Exposed Applications: Glass Fiber Pipe Insulation with PVC jacket. PVC jacket is required in boiler rooms, pump rooms, and large air handler rooms only. Consult UA Project Manager and/or Campus Development Mechanical Engineer.
3. Interior Exposed Applications (Mechanical Rooms): Glass Fiber Pipe Insulation.
4. Exterior Applications: Cellular Glass Pipe Insulation with Aluminum Jacket and Heat Trace.

23 08 00 - Commissioning of HVAC

A. Codes and Standards

1. Codes and Standards: The University of Alabama falls under the jurisdiction of the State of Alabama Division of Construction Management. At the time of development of this design guideline the Energy Standard in effect for the State of Alabama is ANSI/ASHRAE/IESNA Standard 90.1-2013 “Energy Standard for Buildings Except Low-Rise Residential.” This standard requires HVAC commissioning of buildings with project areas greater than 50,000 SF.
2. The University of Alabama also encourages commissioning of buildings or portions of buildings with greater than 16,000 SF in project area for all core campus projects, buildings for special purpose, or buildings housing archival or sensitive items. Projects funded in their entirety by UA affiliated entities (fraternities, sororities, certain retail entities) will be provided commissioning services at the discretion of the particular entity. Contact your project manager for details.

B. Commissioning Agent

1. Engaged directly by UA typically after A/E team is selected and programming is complete.
2. Projects with greater than 50,000 SF in project area to include design phase and construction phase commissioning services.
 - a. Review schematic design/systems selection (30% Narrative)
 - b. Review design development drawings (60% Review)
 - c. Review 90% design documents.
 - d. Review 100% design documents.
 - e. Review VE proposals.
 - f. Review Supplemental Instructions
 - g. Review submittals and coordination drawings.
 - h. Generate test procedures and reports.
 - i. Review and verify TAB and test reports.



UA Design & Construction Guidelines

- j. Conduct Commissioning Meetings, generate agendas and meetings.
 - k. Generate Issue logs and monitor resolution.
 - l. Generate Training plans.
 - m. Generate Preliminary Construction Cx Report (prior to issue of Certificate of Occupancy), including issues report.
 - n. Generate Final Construction Cx report including issues resolution log. Construction Cx report to include submittals and all design documents including supplemental instructions.
3. Projects with less than 50,000 SF in project area but greater than 16,000 SF in project area are to be provided construction phase commissioning services only.
- a. Review submittals and coordination drawings.
 - b. Generate test procedures and reports.
 - c. Review and verify TAB and test reports.
 - d. Conduct Commissioning Meetings, generate agendas and meetings.
 - e. Generate Issue logs and monitor resolution.
 - f. Generate Training plans.
 - g. Generate Preliminary Construction Cx Report (prior to issue of Certificate of Occupancy), including issues report.
 - h. Generate Final Construction Cx report including issues resolution log. Construction Cx report to include submittals and all design documents including supplemental instructions.

C. Systems Requiring Commissioning

1. HVAC Systems – note that all equipment shall be functionally tested and observed by the commissioning agent, this includes all fan coil units and terminal units. Unless directed otherwise by the UA Project Manager, spot checking or testing only a percentage (ex. 25%) of equipment is not acceptable.
2. Emergency Generator Systems and Automatic Transfer Switches (if applicable).

D. Project Integration

1. Where design and construction phase commissioning is being provided, the following specification sections will be provided by the commissioning agent to the designer of record for incorporation into the contract documents:
 - a. 01 91 13 – General Commissioning Requirements
 - b. 23 08 00 – Commissioning of Mechanical Systems
 - c. 26 08 00 – Commissioning of Electrical Systems



2. Where only construction phase commissioning is being provided, the following specification sections will be provided by the designer of record for incorporation into the contract documents:
 - a. 01 91 13 – General Commissioning Requirements
 - b. 23 08 00 – Commissioning of Mechanical Systems
 - c. 26 08 00 – Commissioning of Electrical Systems

Section 23 09 00 - Instrumentation and Control for HVAC

A. Instrumentation and Control - General

1. The University of Alabama's standard control system for new construction and building renovations is the Distech Eclipse BACnet/IP building automation system. For additional information and system requirements, see Division 25 – Integrated Automation Design Guideline.

B. Electrical Systems for HVAC Control

1. Show dedicated 120VAC power circuits for controls applications on the construction documents. Power circuit location and sizing shall be coordinated with HVAC equipment and control device power needs and locations. Controls components shall not be powered by HVAC equipment circuits.
2. Dedicated control power circuits shall be on standby and/or emergency power as dictated by the equipment controlled, i.e. provide standby HVAC control power when the equipment served is on standby power. Control systems for laboratory control applications shall be on standby power.
3. Natural Gas leak detection and carbon monoxide sensors shall be provided for all mechanical rooms, boiler rooms, closets, mezzanines, attics, etc. where natural gas fired appliances/equipment are installed. Detectors shall be connected to the building fire alarm system and shall shut down equipment upon alarm. Coordinate with Electrical Engineer.

C. Pneumatic Control Systems for HVAC

1. Pneumatic controls should be avoided wherever possible. In general, existing pneumatic control systems are to be replaced with DDC systems. Exceptions may be granted for special applications as required.

D. Control System Devices for Plumbing Components

1. For facilities with large domestic water use (kitchens, athletic facilities, dormitories, etc.) – provide temperature sensors to monitor domestic hot water supply temperatures for each system delivering different water temperatures (i.e. 140F system, 120F system) and provide alarm if temperature drops below setpoint.
2. For facilities with domestic water booster pumps, provide pressure sensor in piping downstream of booster pump with display at DDC system user interface. Provide alarm signal if pressure drops below predetermined setpoint.
3. Elevator sump pumps and foundation drain sump pumps shall be monitored by the BAS and generate alarm notifications of pump operation. Coordinate with plumbing design.



E. Control System Monitoring for Other Building Systems

1. The BAS Controls System shall monitor temperature and provide alarms for walk-in type coolers and freezers serving in kitchens and other cold storage applications.
2. The BAS Controls System shall monitor generator run and trouble/E-stop.

F. Specific Control System Requirements

1. Air Handling Units:
 - a. Where air handlers utilize fan arrays, the BAS Controls System shall monitor status and provide alarms for each fan in array with CTs for each fan.
 - b. On air handling units, add the following freeze protection sequence at a minimum. Some installations and situations may warrant additional freeze protection measures: When the outside air temperature is below 30F (adjustable), chilled water and hot water control valves shall modulate to minimum 25% open position. When either valve is needed to maintain their corresponding setpoint, the valve shall modulate from 25-100%. As OA temperature increases to 32F (adjustable), the minimum valve positions shall return to 0%.

Section 23 20 00 - HVAC Piping and Pumps

A. Hydronic Piping

1. Manufacturers: At consultant's discretion unless noted otherwise below. Note that all steel piping is required to be of domestic origin by General Conditions of the Contract Section "Use of Foreign Materials" and Article 39-3-4, Code of Alabama (1975).
2. Materials
 - a. Chilled and Hydronic Hot Water Piping, Above Grade, 2" and smaller:
 - 1) ASTM B88, type L, hard drawn copper tubing. ASME B16.22 wrought copper fittings. Lead-free solder copper joints or press fittings equal to Viega or Nibco.
 - b. Chilled and Hydronic Hot Water Piping, Above Grade, larger than 2":
 - 1) ASTM A53, Schedule 40 carbon steel. ASME B16.3, ASTM A234 forged steel fittings and ASME B16.5, ASTM A105 150# weld-neck or slip-on flanged fittings. Flanges to be compatible with connected equipment (e.g. flat faced flange for cast iron, flat face pump connection and raised face flange for control valve with raised face flange connection). AWS D1.1 butt-weld joints.
 - c. Chilled and Hydronic Hot Water Piping, Below Grade:
 - 1) Pipe Material: ASTM A53, Schedule 40 carbon steel. ASME B16.3, ASTM A234 forged steel fittings and ASME B16.5, ASTM A105 150# weld-neck or slip-on flanged fittings. Flanges to be compatible with connected equipment (e.g. flat faced flange for cast iron, flat face pump connection and raised face flange for control valve with raised face flange connection). AWS D1.1 butt-weld joints.



- 2) Insulation: Pipe and fittings shall be pre-insulated by piping manufacturer. Joints to be insulated using factory provided field insulation kits. Insulation shall be urethane with HDPE jacket. Basis of design: Thermacor Ferro-Therm SC.
- d. Condenser Water Piping, Above Grade:
 - 1) ASTM A53, Schedule 40 carbon steel. ASME B16.3, ASTM A234 forged steel fittings and ASME B16.5, ASTM A105 150# weld-neck or slip-on flanged fittings. Flanges to be compatible with connected equipment (e.g. flat faced flange for cast iron, flat face pump connection and raised face flange for control valve with raised face flange connection). AWS D1.1 butt-weld joints.
 - e. Condenser Water Piping, Below Grade:
 - 1) Carbon Steel Piping:
 - i. Pipe Material: ASTM A53, Schedule 40 carbon steel. ASME B16.3, ASTM A234 forged steel fittings and ASME B16.5, ASTM A105 150# weld-neck or slip-on flanged fittings. Flanges to be compatible with connected equipment (e.g. flat faced flange for cast iron, flat face pump connection and raised face flange for control valve with raised face flange connection). AWS D1.1 butt-weld joints.
 - ii. Jacketing: Pipe and fittings shall be pre-jacketed by piping manufacturer. Joints to be jacketed using factory provided field jacketing kits. Jacket to be of HDPE construction. Basis of design: Thermacor Ferro-Therm SC (w/o insulation).
 - 2) HDPE Piping:
 - i. Pipe Material: PE 3608 per ASTM D3350. SDR 13.5 with pressure rating of 128 psig. PE3608 fittings. Butt fusion joints & transition fittings.
 - ii. Provide tracer wire attached to top of both condenser water supply and return piping.
3. General
 - a. Use of Grooved Couplings and Fittings in Hydronic Piping Systems is prohibited. If equipment connections (e.g. chillers) require grooved fittings, provide grooved to flanged transition fitting at equipment.
 - b. Reducing Fittings: Select type and orientation of reducing fittings to allow gravity drainage.
 - c. Dielectric Protection: Where dissimilar piping materials (steel and copper) are connected, install a dielectric nipple for pipe sizes 2" and less. For pipe sizes 2 1/2" and above, install flanges with dielectric insulation kit.
 - d. Where piping penetrates exterior walls or floors below grade, provide pipe penetration seal kit equal to Link-Seal. Coordinate pipe insulation, sleeve and/or core drill requirements with structural and architectural requirements during development of construction documents.
 - e. Where hydronic piping penetrates floors, provide fire-rated watertight sleeve assembly equal to 3M Fire Barrier Cast-in Device.



UA Design & Construction Guidelines

- f. Connections to existing carbon steel lines shall be done via hot tap or saddle tee installed using a line stop system.
- g. At building control joints expansion loops shall be installed in piping to allow for movement.
- h. Design and detail coil piping requirements to include a valved coil bypass to allow flushing and cleaning of piping without flowing water through the coils. This includes AHU coils and hot water coils at terminal units. Valve handles shall be removed upon completion of flushing and cleaning.
- i. HVAC condensate drain piping on roofs shall terminate at nearest roof drain.
- j. Testing and flushing:
 - 1) Weld testing shall be required and performed by UA's third-party inspection agent. Project specifications shall clearly indicate that welds are not to be UT tested if they fail a visual test per AWI standards. Additionally, project specification shall require the contractor to produce "weld map" drawings to be provided to the Owner and third-party inspection agent for tracking welds.
 - 2) Flushing shall be performed per project specifications and Veolia requirements. Ensure that the water used for flushing is clean prior to commencement of flushing procedures. Veolia to confirm/verify that the methods of their flushing plan have been completed prior to final water tests (ie. Blowdown of low point drains, clean strainers, etc.). UA is to be present with the GC and mechanical subcontractor during final water sampling to ensure the water meets UA standards prior to opening up to central plant and/or certifying building systems.
 - 3) A project's hydronic system pumps shall not be used for flushing and cleaning purposes, separate flushing pump, provided by the contractor, shall be used.
 - 4) The mechanical contractor, as part of the normal submittal process, shall submit a hydronic system flushing and cleaning plan for review by the EOR and UA. The plan shall include procedures for flushing, cleaning, and treatment, chemicals used, target water quality upon completion of each stage, and estimated duration of flushing and cleaning process for each specific system.

B. Hydronic Piping Specialties

- 1. Manufacturers: At consultant's discretion, unless noted otherwise below.
- 2. Expansion Tanks: Bladder type with flexible EPDM bladder for temperature compatibility for both hydronic hot and cold water systems.
- 3. Automatic Air Vents: Float type with isolating valve. Run ¼" soft copper drain line to nearest drain. Install at system high points in piping mains. Locations of automatic air vents to be shown on plans in construction documents.
- 4. Manual Air Vents: Provide at all system high points where automatic air vents are not provided.
- 5. Air Eliminator/Dirt Separator:
 - a. Provide at point of system lowest pressure and highest temperature in hydronic hot water systems.



- b. Provide on chilled water return line just upstream of decoupling line in stand-alone primary/secondary chilled water systems.
- c. Provide on hydronic hot water and chilled water supply lines connected to the central campus distribution system at building entry points.
- d. Provide line size bypass to allow service of separator without system shutdown.
- e. Description: In-line coalescing type air eliminator and dirt separator with air vent, skim valve and full size blow down line to drain.
- f. Manufacturers:
 - 1) Spirothern
 - 2) Armstrong
 - 3) Bell & Gossett
 - 4) Wessels

C. Hydronic Pumps

- 1. Manufacturers:
 - a. Armstrong
 - b. Bell & Gossett
 - c. Taco
 - d. WDM
 - e. Patterson
- 2. Vertical In-Line Pumps:
 - a. Use of vertical in-line pumps is preferred, but not mandatory – other types of pumps may be used if geometry or pressure/flow characteristics dictate.
 - b. Pumps shall be provided with split-coupled pump shaft and coupling guard.
 - c. Seals shall be outside balanced mechanical type with carbon rotating ring held against a silicon carbide seat by a stainless steel spring.
- 3. Sizing/Selection:
 - a. Provide redundant lag or standby pumps to allow for continued system operation when a pump is down for service.
 - b. For variable flow systems, the lead and lag pumps may be sized for 80% of connected load.



- c. For constant flow systems, the lead and standby pumps shall be sized for 100% of connected load.
4. General:
 - a. Each pump size is to be provided with a spare seal kit to be turned over to the UA HVAC Shop.

23 30 00 – HVAC Air Distribution

A. Ducts

1. Medium pressure duct testing shall be witnessed by UA appointed personnel (or UA third party inspectors) and performed per SMACNA.
2. Duct seal class shall be SMACNA Seal Class A requiring all transverse, longitudinal, and duct wall penetrations to be sealed. This applies to all supply, return, outside air, and exhaust ducts.
3. All ductwork located in inaccessible ceiling spaces or chases shall be pressure tested prior to covering up.
4. Grease Duct shall be welded carbon steel not stainless steel. In exposed spaces where aesthetics is of concern, grease duct may be wrapped with stainless steel jacketing. Design documents shall clearly detail method of support and installation including required clearances and access to grease duct cleanout ports.
5. Flexible insulated duct shall be limited to 5 feet in length and only used on supply duct connections to diffusers. In areas with low ceiling spaces, rigid duct elbows shall be used at connections to diffusers.
6. Flexible insulated duct shall not be used on inlets to VAV terminal units.
7. Provide duct access for smoke testing of duct smoke detectors on return air duct approximately 5' upstream of detector.

B. Diffusers

1. In new construction, the preferred lay-in ceiling diffuser type is plaque face style equal to Titus Omni. Insulate back side of diffusers in potentially high humidity environments.
2. In renovations or additions, diffusers shall generally match the style of those in existing spaces within that building unless otherwise determined by the project manager or UA design staff.

23 38 00 – Ventilation Hoods



- A. Kitchen Grease Hoods: Where kitchen grease hoods are installed in a building, the grease hood fire suppression system design shall be included in the construction administration submittal process for review by the engineer of record, UA Campus Development Mechanical Engineer, and the UA Campus Development Building Life Safety Inspector.

23 52 00 – Heating Boilers

- A. Heating boiler type shall be project and application specific and shall be determined with the input from the UA Campus Development Mechanical Engineer and Project Manager. Select boilers to maximize turndown.
- B. Boiler installation must conform to Alabama State Boiler and Pressure Vessel Safety Act.
- C. General:
 - 1. Boilers shall come with low water cutoff (manual reset), dual aqua stat high limit control with manual reset, remote aqua stat, outside air reset, gas cock, gas pressure regulator, 100% flame safeguard with manual reset, pressure relief valve, full shutoff valve, and control panel.
 - 2. Where applicable, add domestic tube bundle heat exchanger.
 - 3. Outside air reset for non-condensing boilers shall be: 160F water when outside air is 90F, to 180F when outside air is 10F.
 - 4. No aluminum heat exchangers.
 - 5. Boiler treatment for new systems to match campus standard water treatment.
- D. Design the system including appropriate connections such that, during construction, pipe cleaning and flushing can be conducted without contamination of the boiler. Design shall require provision of conical startup strainers at the boiler inlets and fine mesh pump startup strainers. Design shall incorporate temporary bypasses of heating coils to avoid fouling coils during flushing and cleaning.
- E. Approved boiler manufacturers.
 - 1. Condensing:
 - a. Lochinvar Crest or Knight depending on capacity requirement.
 - b. Camus DynaForce
 - c. Fulton Endura
 - d. Cleaver Brooks ClearFire
 - e. Laars Magnatherm
 - 2. Near-Condensing:



UA Design & Construction Guidelines

- a. Lars Omnitherm
- b. Lochinvar Powerfin
- c. Camus DynaFlame

23 65 00 – Cooling Towers

- A. General: Cooling tower design selections shall include gear box drives not belt drives.

23 70 00 – Central HVAC Equipment

- A. Installation of roof top AHUs should be avoided. When roof top AHUs must be installed, the design and installation should be performed in a way which minimizes the possibility of water entering into the building due to a coil or piping leak. This may include utilizing horizontal discharge units and installation of AHUs on support structure above the roofing.
- B. On air handlers with fan arrays, provide each fan with backdraft damper.

Change Log – 23 00 00

Description of Change	Sheet or Drawing	Date
Added drawing requirements	230100.O.1.c	08/2020
Added requirements for area of accessibility	230100	08/2020
Added items for clarity of documents	230100.O.1.a	08/2020
Added clarity of TAB requirements	230593.C/D/E/F	08/2020
Updated pipe insulation requirements	230719	08/2020
Added fan speed control	230900.G.6.d	08/2020
Added building movement accommodation	232000.A.3.g	08/2020
Added duct requirements	233000.A	08/2020
Added diffuser requirements	233000.B	08/2020
Created section for grease hoods	233800	08/2020
Created section for boilers	235200	08/2020
Added requirement for BTU metering	230519	07/2021
Added requirement for chilled water system startup	230716.D	07/2021
Added requirement for chilled water system startup	230719.I	07/2021
Added carbon monoxide detection	230900.H.3	07/2021
Added coil bypass requirements	232000.A.3.h	07/2021
Added flushing requirements	232000.A.3.j	07/2021
Updated economizer requirement	230100.C.1	01/2023
Added requirement for contractor's responsibilities with existing systems	230100.N.1	01/2023
Added previously documented mechanical equipment room requirements	230100.I	01/2023
Updated mfr's model number and communication	230514.A/E	01/2023
Added requirements for BTU meters	230519.C.3	01/2023
Added anchoring requirements	230529.E	01/2023
Updated Mechanical Equipment Room requirements	230523	01/2023
Revision to HVAC controls requirements (See new section Division 25)	230900	01/2023
Added condensate drain requirement	232000.A.3.i	01/2023
Added LED indicator for heat trace	230533.F	09/2023
Added restriction for roof mounted air handlers	237000	09/2023
Added boiler manufacturer	235200.E.1	09/2023
Added temporary conditioning section	230100.P.1.j	11/2024
Added BAS monitoring of generator	230900.E.2	11/2024
Added duct access for smoke testing	233000.A.7	11/2024
Added other acceptable testing certifications	230593.A	11/2024
Added hangers located within 12" of direction change	230529.C.2	11/2024
Clarified where pipe PVC jacket is required	230719.(J,K,L,M,N).2	11/2024
Added unique pipe labeling for Central Thermal	230553.B.4	11/2024
Noted foreign materials compliance in valve section	230523.A.6	11/2024
Changed valve type for direct bury valves from butterfly to ball valves	230523.B.4	11/2024
Added cooling tower section for gear box driven fans	236500.A	11/2024
Added requirement for pumps with spare seal kit	232000.C.4	11/2024
Changes to hydronic pipe smaller than 2"	232000.A.2.a	11/2024
Change exterior duct system	230713.E.3 & F.2	11/2024

