

TABULATION OF BIDS



Project Name
Bryce Lawn Tornado
Shelter

Bid Due
Wednesday, March 2, 2022 at 2:00 pm

Architect/Engineer
Adams Stewart Architects, LLC
22615 Highway 59 North
Robertsdale, AL 36567
phone: (251) 947-3864

UA Project No.
356-21-2318

Bid Location
405 Cahaba Circle
Tuscaloosa, Alabama 35404

FUNDS AVAILABLE: Seven million, nine hundred thousand dollars and 00/100 (\$7,900,000.00)


BIDS SHALL BE VALID FOR: Sixty (60) Calendar Days

CONSTRUCTION COMPLETION DATE: April 30, 2023

CONTRACTOR	J.T. Harrison Construction Co, Inc. 5870 Charlie Shirley Road Northport, AL 35473 GC Lic. # 20245	WAR Construction, Inc. P.O. Box 1218 Tuscaloosa, AL 35403 GC Lic. # 6418	Kyser Construction, LLC 214 Hargrove Road East Tuscaloosa, AL 35401 GC Lic. # 42467
ADDENDA ONE - FOUR	☒ Yes ☐ No	☒ Yes ☐ No	☒ Yes ☐ No
LICENSE # ON ENVELOPE	☒ Yes ☐ No	☒ Yes ☐ No	☒ Yes ☐ No
BONDING COMPANY OR BID DEPOSIT	Travelers Casualty & Surety Company of America	The Cincinnati Insurance Company	The Cincinnati Insurance Company
TOTAL UNIT PRICE ITEMS - BASE BID <i>See Pages 2-6.</i>	\$ 1,613,651.80	\$ 1,500,679.09	\$ 1,502,416.09
BASE BID ON PROPOSAL	\$ 8,000,000.00	\$ 8,200,000.00	\$ 8,200,000.00
ENVELOPE ADJUSTMENT	(427,000.00)	(272,000.00)	(256,000.00)
UNIT PRICE ERRORS ADJUSTMENT	(3,822.25)	-	-
ADJUSTED BASE BID	7,569,177.75	7,928,000.00	7,944,000.00
ALTERNATE #1 <i>Description on back of page</i>	360,000.00	363,000.00	475,000.00
ENVELOPE ADJUSTMENT	(10,500.00)	(5,300.00)	(56,000.00)
SUBTOTAL	7,918,677.75	8,285,700.00	8,363,000.00
ALTERNATE #2 <i>Description on back of page</i>	440,000.00	425,000.00	425,000.00
ENVELOPE ADJUSTMENT	-	-	-
SUBTOTAL	8,358,677.75	8,710,700.00	8,788,000.00
ALTERNATE #3 <i>Description on back of page</i>	146,000.00	147,500.00	155,000.00
ENVELOPE ADJUSTMENT	(24,000.00)	-	-
SUBTOTAL	8,480,677.75	8,858,200.00	8,943,000.00
ALTERNATE #4 <i>Description on back of page</i>	1,600.00	1,700.00	4,700.00
ENVELOPE ADJUSTMENT	-	-	-
TOTAL BID W/ ALTERNATES	\$ 8,482,277.75	\$ 8,859,900.00	\$ 8,947,700.00

• Indicates Corrected Total

I CERTIFY THIS IS A TRUE AND ACCURATE TABULATION OF THE BIDS RECEIVED ON THE CAPTIONED PROJECT.


Andrea Pearson Tyner, J.D.
Contract Administrator
The University of Alabama

Alternate Descriptions:

Alternate #1: Green Room

Alternate #2: AV System

Alternate #3: Patio Cover

Alternate #4: Wind Screen for Lay Down Fence

CONTRACTOR	J.T. Harrison Construction Co, Inc.		WAR Construction, Inc.		Kyser Construction, LLC	
	5870 Charlie Shirley Road Northport, AL 35473 GC Lic. # 20245		P.O. Box 1218 Tuscaloosa, AL 35403 GC Lic. # 6418		214 Hargrove Road East Tuscaloosa, AL 35401 GC Lic. # 42467	

Line No.	Estimated Quantity	Unit	Description	Unit Price	Total	Unit Price	Total	Unit Price	Total
CIVIL/SITE ITEMS									
100	1	Ls.	Mobilization / Demobilization	\$ 4,509.00	\$ 4,509.00	\$ 18,000.00	\$ 18,000.00	\$ 17,300.00	\$ 17,300.00
101	1	Ls.	Demolition, Clearing, and Grubbing	\$ 28,404.00	\$ 28,404.00	\$ 73,000.00	\$ 73,000.00	\$ 72,315.00	\$ 72,315.00
102	1	Ls.	Construction Layout	\$ 14,580.00	\$ 14,580.00	\$ 13,000.00	\$ 13,000.00	\$ 13,500.00	\$ 13,500.00
103	1	Ls.	GPS of Utilities and As-Built Drawings	\$ 3,240.00	\$ 3,240.00	\$ 5,900.00	\$ 5,900.00	\$ 4,500.00	\$ 4,500.00
104	1	Ls.	UA Bronze Utility Marker Installation	\$ 1,620.00	\$ 1,620.00	\$ 3,360.00	\$ 3,360.00	\$ 1,000.00	\$ 1,000.00
105	1	Ls.	ADEM NPDES Stormwater Permitting	\$ 11,070.00	\$ 11,070.00	\$ 7,500.00	\$ 7,500.00	\$ 10,850.00	\$ 10,850.00
106	1	Ls.	Construction Exit Pad(s) with Vehicle Wash Rack	\$ 3,780.00	\$ 3,780.00	\$ 11,000.00	\$ 11,000.00	\$ 10,750.00	\$ 10,750.00
107	1,000	Lf.	Erosion Control Silt Fence	\$ 4.32	\$ 4,320.00	\$ 3.75	\$ 3,750.00	\$ 3.60	\$ 3,600.00
108	500	Lf.	Erosion Control Wattle	\$ 4.32	\$ 2,160.00	\$ 3.60	\$ 1,800.00	\$ 3.60	\$ 1,800.00
109	4	each	Erosion Control Inlet Protection	\$ 378.00	\$ 1,512.00	\$ 4.00	\$ 16.00	\$ 495.00	\$ 1,980.00
110	100	ton	Crushed Limestone for Temporary Access Road (ALDOT 825 Type 'B')	\$ 32.40	\$ 3,240.00	\$ 39.00	\$ 3,900.00	\$ 38.50	\$ 3,850.00
111	1	Ls.	Earthwork	\$ 231,561.72	\$ 231,561.72	\$ 105,000.00	\$ 105,000.00	\$ 103,050.00	\$ 103,050.00
112	1,000	s.y.	Geotextile Fabric (To Be Used Only as Directed by the Owner's Representative)	\$ 4.86	\$ 4,860.00	\$ 2.50	\$ 2,500.00	\$ 2.40	\$ 2,400.00
113	6,000	c.y.i.p.	Unsuitable Material Removal / Replacement (Below Subgrade Elevation and Includes Debris Removal)	\$ 24.76	\$ 148,560.00 +	\$ 20.00	\$ 120,000.00	\$ 19.00	\$ 114,000.00
114	1	Ls.	Topsoil Replacement (Minimum 4" In-Place Thickness)	\$ 16,200.00	\$ 16,200.00	\$ 34,500.00	\$ 34,500.00	\$ 8,540.00	\$ 8,540.00
115	800	Lf.	Type "A" Curb (6")	\$ 23.76	\$ 19,008.00	\$ 16.00	\$ 12,800.00	\$ 21.00	\$ 16,800.00
116	1,100	s.y.i.p.	Concrete Sidewalks, Patio and Pads (Includes Portions with Integral 6" Curb and ADA Ramps)	\$ 70.20	\$ 77,220.00	\$ 60.00	\$ 66,000.00	\$ 118.00	\$ 129,800.00
117	60	s.y.i.p.	Concrete Pavement (Minimum 7" thick, 4500 psi concrete with Tufmax DOT or Approved Equal Fiber Reinforcement at 3 lbs/cv)	\$ 77.76	\$ 4,665.60	\$ 80.00	\$ 4,800.00	\$ 159.00	\$ 9,540.00
118	220	s.y.i.p.	Concrete Sidewalk Removal and Replacement (Along Campus Drive) (Includes ADA Ramps)	\$ 81.00	\$ 17,820.00	\$ 85.00	\$ 18,700.00	\$ 20.00	\$ 4,400.00
119	1,380	s.y.i.p.	Crushed Aggregate Limestone Base Course, ALDOT 825 Type 'B' (4" Compacted Thickness)	\$ 10.80	\$ 14,904.00	\$ 11.00	\$ 15,180.00	\$ 12.00	\$ 16,560.00
120	1	Ls.	Brick Paver Plaza (Includes Stone Base)	\$ 14,871.60	\$ 14,871.60	\$ 14,000.00	\$ 14,000.00	\$ 13,770.00	\$ 13,770.00
121	4,800	s.y.i.p.	Improved Bituminous Concrete Wearing Surface Layer, ALDOT 424A, 3/8" Maximum Aggregate Size Mix, ESAL Range B With Tack Coat (1.5" Compacted Thickness)	\$ 9.50	\$ 45,600.00 +	\$ 9.00	\$ 43,200.00	\$ 8.80	\$ 42,240.00
122	4,800	s.y.i.p.	Improved Bituminous Concrete Binder Layer, ALDOT 424B, 1" Maximum Aggregate Size Mix, ESAL Range B (3" Compacted Thickness)	\$ 16.37	\$ 78,576.00 +	\$ 15.30	\$ 73,440.00	\$ 15.16	\$ 72,768.00
123	4,800	s.y.i.p.	Crushed Aggregate Limestone Base Course, ALDOT 825 Type 'B' (8" Compacted Thickness, Placed in Two Equal Layers)	\$ 16.07	\$ 77,136.00 +	\$ 15.00	\$ 72,000.00	\$ 14.88	\$ 71,424.00
124	1	each	Precast Concrete Sanitary Sewer Manhole	\$ 3,067.20	\$ 3,067.20	\$ 3,600.00	\$ 3,600.00	\$ 3,560.00	\$ 3,560.00
125	1	each	Sanitary Sewer Manhole Ring and Cover	\$ 475.20	\$ 475.20	\$ 450.00	\$ 450.00	\$ 440.00	\$ 440.00
126	40	Lf.	6" SDR 26 PVC Sanitary Sewer	\$ 48.38	\$ 1,935.20 +	\$ 55.00	\$ 2,200.00	\$ 55.00	\$ 2,200.00
127	140	Lf.	4" SDR 26 PVC Sanitary Sewer (Includes Cleanouts & Fittings)	\$ 52.01	\$ 7,281.40 +	\$ 49.00	\$ 6,860.00	\$ 48.50	\$ 6,790.00
128	2	each	4" Solvent Weld Caps	\$ 8.04	\$ 16.08 +	\$ 5.00	\$ 10.00	\$ 5.00	\$ 10.00
129	40	Lf.	Post Construction CCTV of Sanitary Sewer	\$ 6.48	\$ 259.20	\$ 7.50	\$ 300.00	\$ 7.50	\$ 300.00
130	1	each	Connect to Existing Sanitary Sewer Manhole	\$ 1,944.00	\$ 1,944.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00
131	1	each	Adjust Existing Sanitary Sewer Manhole to Finished Grade	\$ 648.00	\$ 648.00	\$ 1,400.00	\$ 1,400.00	\$ 1,350.00	\$ 1,350.00
132	1	each	Inside Drop Connection for Existing Sanitary Sewer Manhole	\$ 1,737.43	\$ 1,737.43	\$ 1,500.00	\$ 1,500.00	\$ 1,450.00	\$ 1,450.00
133	1	each	6" Post Siamese Fire Department Connection	\$ 4,003.56	\$ 4,003.56	\$ 3,800.00	\$ 3,800.00	\$ 3,750.00	\$ 3,750.00
134	1	each	6" Detector Check Assembly	\$ 8,804.16	\$ 8,804.16	\$ 11,400.00	\$ 11,400.00	\$ 11,315.00	\$ 11,315.00
135	1	each	2" Domestic Meter Assembly	\$ 994.11	\$ 994.11	\$ 750.00	\$ 750.00	\$ 750.00	\$ 750.00
136	1	each	2" Irrigation Meter Assembly	\$ 994.11	\$ 994.11	\$ 750.00	\$ 750.00	\$ 750.00	\$ 750.00
137	2	each	Fire Hydrant Assembly (Includes Tee and Valve)	\$ 5,182.43	\$ 10,364.86 +	\$ 6,000.00	\$ 12,000.00	\$ 5,895.00	\$ 11,790.00
138	500	Lf.	24" CL 250 Ductile Iron Watermain	\$ 195.86	\$ 97,930.00 +	\$ 215.00	\$ 107,500.00	\$ 214.00	\$ 107,000.00
139	240	Lf.	6" CL 350 Ductile Iron UA Fire Watermain	\$ 42.69	\$ 10,245.60 +	\$ 41.00	\$ 9,840.00	\$ 41.00	\$ 9,840.00
140	120	Lf.	2 - 1/2" HDPE UA Domestic Watermain (Includes Fittings)	\$ 37.80	\$ 4,536.00	\$ 15.00	\$ 1,800.00	\$ 15.00	\$ 1,800.00
141	2	each	24" x 24" Watermain MJ Tapping Sleeve (Mueller H-615 or Equal) and Valve with Valve Box	\$ 62,173.44	\$ 124,346.88	\$ 44,000.00	\$ 88,000.00	\$ 43,265.00	\$ 86,530.00
142	2	each	24" Line Stop for Temporary Isolation	\$ 26,551.80	\$ 53,103.60	\$ 25,700.00	\$ 51,400.00	\$ 25,700.00	\$ 51,400.00
143	2	each	24" Pigging Launcher/Receiver	\$ 19,478.88	\$ 38,957.76	\$ 1,000.00	\$ 2,000.00	\$ 1,000.00	\$ 2,000.00
144	2	each	Cut/Cap Existing 24" Watermain (Includes Materials)	\$ 7,217.64	\$ 14,435.28	\$ 14,000.00	\$ 28,000.00	\$ 13,765.00	\$ 27,530.00
145	1	each	6" Valve and Valve Box	\$ 1,004.26	\$ 1,004.26	\$ 1,050.00	\$ 1,050.00	\$ 1,050.00	\$ 1,050.00
146	2	each	4" Valve and Valve Box	\$ 832.76	\$ 1,665.52 +	\$ 625.00	\$ 1,250.00	\$ 625.00	\$ 1,250.00
147	2	each	End Line Restraint	\$ 4,509.00	\$ 9,018.00	\$ 850.00	\$ 1,700.00	\$ 850.00	\$ 1,700.00
148	3,000	lbs	Watermain Fittings (Ductile Iron)(Compact)	\$ 9.26	\$ 27,780.00 +	\$ 14.00	\$ 42,000.00	\$ 14.00	\$ 42,000.00
149	3	each	Watermain Connection	\$ 1,620.00	\$ 4,860.00	\$ 4,000.00	\$ 12,000.00	\$ 4,000.00	\$ 12,000.00
150	1	Ls.	Allowance for City of Tuscaloosa Water Meter Permit Fee(s)	\$ 5,830.09	\$ 5,830.09	\$ 5,830.09	\$ 5,830.09	\$ 5,830.09	\$ 5,830.09
151	1	Ls.	Overhead and Profit Associated with Item 150	\$ 648.00	\$ 648.00	\$ 580.00	\$ 580.00	\$ 600.00	\$ 600.00
152	1	each	Storm Structure, Inline Drain	\$ 1,611.36	\$ 1,611.36	\$ 1,570.00	\$ 1,570.00	\$ 1,570.00	\$ 1,570.00
153	2	each	Storm Drainage Structure, Curb Inlet (Double Grate)	\$ 4,510.08	\$ 9,020.16	\$ 8,600.00	\$ 17,200.00	\$ 8,560.00	\$ 17,120.00
154	1	each	Storm Drainage Structure, Grate Inlet	\$ 2,446.20	\$ 2,446.20	\$ 3,600.00	\$ 3,600.00	\$ 3,600.00	\$ 3,600.00
155	1	each	Storm Drainage Structure, 18" Precast Headwall	\$ 1,146.42	\$ 1,146.42	\$ 925.00	\$ 925.00	\$ 925.00	\$ 925.00
156	1	each	Storm Drainage Structure, 12" Sloped Paved Headwall	\$ 800.00	\$ 800.00	\$ 700.00	\$ 700.00	\$ 700.00	\$ 700.00
157	472	Lf.	18" Diameter Storm Sewer	\$ 51.14	\$ 24,138.08 +	\$ 96.00	\$ 45,312.00	\$ 95.50	\$ 45,076.00
158	400	Lf.	12" Diameter Storm Sewer	\$ 85.26	\$ 34,104.00 +	\$ 80.00	\$ 32,000.00	\$ 80.00	\$ 32,000.00
159	200	Lf.	8" Diameter Storm Sewer	\$ 45.10	\$ 9,020.00 +	\$ 50.00	\$ 10,000.00	\$ 50.00	\$ 10,000.00
160	300	Lf.	6" Diameter Storm Sewer	\$ 43.06	\$ 12,918.00 +	\$ 50.00	\$ 15,000.00	\$ 50.00	\$ 15,000.00
161	50	tons	Rip-Rap Class II	\$ 56.16	\$ 2,808.00	\$ 65.00	\$ 3,250.00	\$ 64.00	\$ 3,200.00
162	472	Lf.	Post Construction CCTV of Storm Sewer	\$ 6.00	\$ 2,832.00	\$ 6.00	\$ 2,832.00	\$ 5.50	\$ 2,596.00
163	900	Lf.	Site Constraint Fencing (Post Driven with Wind Screen)	\$ 18.90	\$ 17,010.00	\$ 20.00	\$ 18,000.00	\$ 17.50	\$ 15,750.00

CONTRACTOR				J.T. Harrison Construction Co, Inc.		WAR Construction, Inc.		Kyser Construction, LLC	
				5870 Charlie Shirley Road Northport, AL 35473 GC Lic. # 20245		P.O. Box 1218 Tuscaloosa, AL 35403 GC Lic. # 6418		214 Hargrove Road East Tuscaloosa, AL 35401 GC Lic. # 42467	
164	400	I.f.	Orange "Snow" Fencing (To be Installed as Directed by Owner's Representative)	\$ 4.86	\$ 1,944.00	\$ 3.00	\$ 1,200.00	\$ 2.00	\$ 800.00
165	1	each	20' Wide Double Hung Gate (Construction Fencing)	\$ 453.60	\$ 453.60	\$ 500.00	\$ 500.00	\$ 250.00	\$ 250.00
166	1	each	5' Wide Pedestrian Gate (Construction Fencing)	\$ 270.00	\$ 270.00	\$ 250.00	\$ 250.00	\$ 150.00	\$ 150.00
167	300	I.f.	Relocate Existing Chain Link Fence (Includes Gate)	\$ 15.39	\$ 4,617.00	\$ 12.00	\$ 3,600.00	\$ 12.00	\$ 3,600.00
168	700	I.f.	Black Vinyl Coated Chain Link Fence	\$ 27.76	\$ 19,432.00 +	\$ 32.00	\$ 22,400.00	\$ 25.70	\$ 17,990.00
169	2	each	20' Wide Double Hung Gate (Black Vinyl Coated Chain Link)	\$ 669.60	\$ 1,339.20	\$ 1,200.00	\$ 2,400.00	\$ 620.00	\$ 1,240.00
170	1	each	5' Wide Pedestrian Gate (Black Vinyl Coated Chain Link)	\$ 270.00	\$ 270.00	\$ 600.00	\$ 600.00	\$ 250.00	\$ 250.00
171	220	I.f.	Irrigation Sleeves: Dual Run of 6" and 4" Schedule 40 PVC	\$ 21.60	\$ 4,752.00	\$ 35.00	\$ 7,700.00	\$ 34.00	\$ 7,480.00
172	3	each	UA Permanent Sign Post with Finials	\$ 378.00	\$ 1,134.00	\$ 250.00	\$ 750.00	\$ 325.00	\$ 975.00
173	1	each	Stop Sign	\$ 513.00	\$ 513.00	\$ 500.00	\$ 500.00	\$ 475.00	\$ 475.00
174	2	each	ADA/Van Accessible Sign	\$ 388.80	\$ 777.60	\$ 250.00	\$ 500.00	\$ 250.00	\$ 500.00
175	10	each	Steel Bollards, Fixed	\$ 702.00	\$ 7,020.00	\$ 450.00	\$ 4,500.00	\$ 525.00	\$ 5,250.00
176	1	Ls.	Permanent/Temporary Traffic Striping	\$ 1,563.84	\$ 1,563.84	\$ 7,500.00	\$ 7,500.00	\$ 1,623.00	\$ 1,623.00
177	1	Ls.	Temporary Traffic and Pedestrian Control	\$ 2,700.00	\$ 2,700.00	\$ 4,500.00	\$ 4,500.00	\$ 4,500.00	\$ 4,500.00
178	1	Ls.	Temporary Grassing / Mulching (All Disturbed Areas)	\$ 3,888.00	\$ 3,888.00	\$ 5,000.00	\$ 5,000.00	\$ 4,500.00	\$ 4,500.00
SUB-TOTAL CIVIL/SITE ITEMS				\$	1,434,831.88 •	\$	1,335,105.09	\$	1,340,342.09
LANDSCAPE/IRRIGATION ITEMS									
200	5	each	Trees, Lagerstroemia indica 'Tuscarora' / Tuscarora Crape myrtle (Balled and Burlapped) (10' ht, Mult--trunked)	\$ 313.20	\$ 1,566.00	\$ 290.00	\$ 1,450.00	\$ 290.00	\$ 1,450.00
201	20	each	Trees, Foster Holly / Ilex x attenuata 'Fosterii' (Balled and Burlapped) (10' ht)	\$ 432.00	\$ 8,640.00	\$ 400.00	\$ 8,000.00	\$ 400.00	\$ 8,000.00
202	10	each	Trees, Ilex x Conty 'Liberty' / Liberty Holly (Balled and Burlapped)(Full to Ground) (10' ht)	\$ 756.00	\$ 7,560.00	\$ 700.00	\$ 7,000.00	\$ 700.00	\$ 7,000.00
203	8	each	Trees, Quercus phellos 'Hightower' / Hightower Willow Oak (Balled and Burlapped) (4 1/2"-5" Caliper, 16' Height)	\$ 853.20	\$ 6,825.60	\$ 790.00	\$ 6,320.00	\$ 790.00	\$ 6,320.00
204	2	each	Trees, Ulmus americana 'Princeton' / Princeton Elm (Balled and Burlapped) (4 1/2"-5" Caliper, 16' Height)	\$ 853.20	\$ 1,706.40	\$ 790.00	\$ 1,580.00	\$ 790.00	\$ 1,580.00
205	184	each	Shrubs, Ilex vomitoria 'Nana' / Dwarf Yaupon Holly (7 gal.)	\$ 51.84	\$ 9,538.56	\$ 48.00	\$ 8,832.00	\$ 48.00	\$ 8,832.00
206	37	each	Shrubs, Camellia sasanqua 'Yuletide' / 'Yuletide Sasanqua (7 gal.)	\$ 77.76	\$ 2,877.12	\$ 72.00	\$ 2,664.00	\$ 72.00	\$ 2,664.00
207	66	each	Shrubs, Ilex cornuta 'Carissa' / Carissa Holly (7 gal.)	\$ 51.84	\$ 3,421.44	\$ 48.00	\$ 3,168.00	\$ 48.00	\$ 3,168.00
208	35	each	Shrubs, Rhododendron 'Delaware Valley White' / Delaware Valley White Azalea (7 gal.)	\$ 60.48	\$ 2,116.80	\$ 56.00	\$ 1,960.00	\$ 56.00	\$ 1,960.00
209	180	each	Ground Cover, Liriope muscari 'Big Blue'/Big Blue Liriope (1 gal.)	\$ 6.48	\$ 1,166.40	\$ 6.00	\$ 1,080.00	\$ 6.00	\$ 1,080.00
210	120	each	Ground Cover, Ophiopogon japonicus / Mondo (1 gal.)	\$ 6.48	\$ 777.60	\$ 6.00	\$ 720.00	\$ 6.00	\$ 720.00
211	6,000	s.y.	Sod, Zoysia 'Empire' / 'Empire Zoysia'	\$ 7.56	\$ 45,360.00	\$ 7.00	\$ 42,000.00	\$ 7.00	\$ 42,000.00
212	500	I.f.	Tree Protection Fencing (4' Chainlink)	\$ 16.20	\$ 8,100.00	\$ 15.00	\$ 7,500.00	\$ 8.00	\$ 4,000.00
213	1	each	TSD-PS1-U2 Toro Sentinel 2-Wire Controller (Includes System Lightning Protection, All Parts Necessary for Installation, Programming, and Coordination with UA Irrigation)	\$ 8,424.00	\$ 8,424.00	\$ 7,800.00	\$ 7,800.00	\$ 7,800.00	\$ 7,800.00
214	10	zone	Rotor Zone 1 1/2" (Includes Rainbird PE 1 1/2" Valve with Toro 2-Wire Decoder, Rainbird 5000+ SAM (Or Approved Equal) Couplers Elbows, Pipe, Valve Box	\$ 3,510.00	\$ 35,100.00	\$ 3,250.00	\$ 32,500.00	\$ 3,250.00	\$ 32,500.00
215	1	zone	Spray Zone 1" (Includes Rainbird PE 1" Valve with Toro 2-Wire Decoder, Rainbird 1806 (Or Approved Equal) Couplers Elbows, Pipe, Valve Box	\$ 2,700.00	\$ 2,700.00	\$ 2,500.00	\$ 2,500.00	\$ 2,500.00	\$ 2,500.00
216	1	zone	Spray Zone 1 1/2" (Includes Rainbird PE 1 1/2" Valve with Toro 2-Wire Decoder, Rainbird 1806 (Or Approved Equal) Couplers Elbows, Pipe, Valve Box	\$ 3,780.00	\$ 3,780.00	\$ 3,500.00	\$ 3,500.00	\$ 3,500.00	\$ 3,500.00
217	4	zone	Spray Zone 1 1/2" (Includes Rainbird PE 1 1/2" Valve with Toro 2-Wire Decoder, Rainbird 1812 (Or Approved Equal) Couplers Elbows, Pipe, Valve Box	\$ 4,050.00	\$ 16,200.00	\$ 3,750.00	\$ 15,000.00	\$ 3,750.00	\$ 15,000.00
218	3	each	Hose Bib Zone with Straight Connector (Includes Rainbird PE 1 1/2" Valve with Toro 2-Wire Decoder, Couplers Elbows, Pipe, Jumbo Valve Box, etc.	\$ 540.00	\$ 1,620.00	\$ 500.00	\$ 1,500.00	\$ 500.00	\$ 1,500.00
219	2	each	3" Brass Isolation/Gate Valve in Mainline - Stockham Class 125, B-103 Or Approved Equal (Includes Couplers Elbows, Pipe, Valve Box, etc., to Operate)	\$ 324.00	\$ 648.00	\$ 300.00	\$ 600.00	\$ 300.00	\$ 600.00
220	1,200	I.f.	Irrigation Control Wire	\$ 2.16	\$ 2,592.00	\$ 2.00	\$ 2,400.00	\$ 2.00	\$ 2,400.00
221	750	I.f.	Irrigation Mainline - 3" Class 200 Bell and Gasket (Includes Thrust Blocks, Couplers, Elbows, etc., Required to Connect)	\$ 10.80	\$ 8,100.00	\$ 10.00	\$ 7,500.00	\$ 10.00	\$ 7,500.00
SUB-TOTAL LANDSCAPE/IRRIGATION ITEMS				\$	178,819.92	\$	165,574.00	\$	162,074.00
TOTAL UNIT PRICE ITEMS - BASE BID				\$	1,613,651.80 •	\$	1,500,679.09	\$	1,502,416.09

- Indicates Corrected Total
- + Indicates Summation Error