

TABULATION OF BIDS

THE UNIVERSITY OF
ALABAMA

Project Name

University Boulevard Hackberry to 6th Ave
Infrastructure and Security Improvements

Bid Due

May 11, 2023 3:00 p.m. local time

Architect/Engineer

Thompson Engineering
2900 8th Street
Tuscaloosa, AL 35401
phone: (205) 759-3221

UA Project No.

TRN-23-3296

Bid Location

405 Cahaba Circle
Tuscaloosa, AL 35404

FUNDS AVAILABLE:

Two million, six hundred fifty-seven thousand, four hundred twenty dollars and 00/100 (\$2,657,420.00)

BIDS SHALL BE VALID FOR:

Sixty (60) Days

CONSTRUCTION DURATION:

Project Completion: August 8, 2023

CONTRACTOR				Central Alabama Asphalt & Construction Co., LLC		John Plott Company, Inc.		Price Construction Company, Inc.	
				P. O. Box 20766 Tuscaloosa, AL 35402 (205) 349-0910 GC Lic. #41676		P. O. Box 20183 Tuscaloosa, AL 35402 (205) 345-5678 GC Lic. #9266		P. O. Box 78 Peterson, AL 35478 (205) 553-4520 GC Lic. #15839	
Addenda ONE - THREE				<u>X</u> Yes ___ No		<u>X</u> Yes ___ No		<u>X</u> Yes ___ No	
LICENSE # ON ENVELOPE				<u>X</u> Yes ___ No		<u>X</u> Yes ___ No		<u>X</u> Yes ___ No	
BONDING COMPANY OR BID DEPOSIT				Arch Insurance Company		Western Surety Co.		Cincinnati Insurance Co.	
Item No.	Est. Qty.	Unit	Description	Unit Price	Total	Unit Price	Total	Unit Price	Total
General, Demolition, Clearing, Grubbing, and Earthwork									
1	1	LS	Mobilization and Demobilization	\$ 62,000.00	\$ 62,000.00	\$ 178,706.72	\$ 178,706.72	\$ 80,000.00	\$ 80,000.00
2	1	LS	Demolition, Clearing & Grubbing	\$ 95,000.00	\$ 95,000.00	\$ 93,480.00	\$ 93,480.00	\$ 100,000.00	\$ 100,000.00
3	4,025	SY	Remove Asphalt & Concrete	\$ 14.04	\$ 56,511.00	\$ 58.88	\$ 236,992.00	\$ 25.00	\$ 100,625.00
4	1	LS	Earthwork	\$ 106,500.00	\$ 106,500.00	\$ 236,819.00	\$ 236,819.00	\$ 390,000.00	\$ 390,000.00
5	50	CYIP	Borrow Excavation (A-4 or Better) (Only as Directed by the Owner's Representative)	\$ 75.00	\$ 3,750.00	\$ 40.80	\$ 2,040.00	\$ 100.00	\$ 5,000.00
6	1,700	CYIP	Excavation and Disposal of Unsuitable Material (Only as Directed by the Owner's Representative)	\$ 21.40	\$ 36,380.00	\$ 34.88	\$ 59,296.00	\$ 15.00	\$ 25,500.00
7	1,500	Ton	ALDOT No. 2 Stone for Unsuitable Material Replacement (Only as Directed by the Owner's Representative)	\$ 35.00	\$ 52,500.00	\$ 28.35	\$ 42,525.00	\$ 20.00	\$ 30,000.00
8	3,300	SY	Geosynthetic Reinforcement for Soft Soil Stabilization, Type 3 (Only as Directed by the Owner's Representative)	\$ 2.80	\$ 9,240.00	\$ 5.00	\$ 16,500.00	\$ 3.00	\$ 9,900.00
9	190	CYIP	Topsoil - Onsite Stockpile (4" Thickness)	\$ 70.00	\$ 13,300.00	\$ 63.00	\$ 11,970.00	\$ 71.50	\$ 13,585.00
Base, Pave, and Curb and Gutter Improvements									
10	6	STA	Roadbed Processing	\$ 0.01	\$ 0.06	\$ 997.50	\$ 5,985.00	\$ 500.00	\$ 3,000.00
11	400	SY	Existing Pavement Milling (Approx. 1.5" Thickness)	\$ 7.38	\$ 2,952.00	\$ 5.45	\$ 2,180.00	\$ 5.71	\$ 2,284.00
12	3,420	SY	Crushed Aggregate Limestone Base Course, 825B, Pland Mixed, 12.5" Compacted Thickness	\$ 28.00	\$ 95,760.00	\$ 39.57	\$ 135,329.40	\$ 28.07	\$ 95,999.40

JDR


Initial

Contractor				Central Alabama Asphalt & Construction Co., LLC		John Plott Company, Inc.		Price Construction Company, Inc.	
Item No.	Est. Qty.	Unit	Description	Unit Price	Total	Unit Price	Total	Unit Price	Total
13	1,700	CYIP	Crushed Aggregate Limestone ALDOT No. 825 Type 'B' Select Backfill (Only As Directed by Owner's Representative)	\$ 70.20	\$ 119,340.00	\$ 59.70	\$ 101,490.00	\$ 10.00	\$ 17,000.00
14	3,280	SY	Bituminous Treatment A	\$ 0.10	\$ 328.00	\$ 0.98	\$ 3,214.40	\$ 1.02	\$ 3,345.60
15	985	Gallon	Tack Coat	\$ 5.00	\$ 4,925.00	\$ 4.26	\$ 4,196.10	\$ 4.47	\$ 4,402.95
16	350	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D	\$ 133.00	\$ 46,550.00	\$ 154.30	\$ 54,005.00	\$ 161.65	\$ 56,577.50
17	175	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D	\$ 133.00	\$ 23,275.00	\$ 154.30	\$ 27,002.50	\$ 161.65	\$ 28,288.75
18	830	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D	\$ 143.00	\$ 118,690.00	\$ 127.25	\$ 105,617.50	\$ 133.31	\$ 110,647.30
19	150	Ton	Superpave Bituminous Concrete Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D	\$ 150.00	\$ 22,500.00	\$ 215.99	\$ 32,398.50	\$ 226.27	\$ 33,940.50
20	55	SY	Concrete Pavement (5.5" Thick)	\$ 120.00	\$ 6,600.00	\$ 149.58	\$ 8,226.90	\$ 139.00	\$ 7,645.00
21	750	SY	Concrete Sidewalk (6" Thick) (w/ Stone)	\$ 106.20	\$ 79,650.00	\$ 103.00	\$ 77,250.00	\$ 104.00	\$ 78,000.00
22	25	LF	Type C Combination Curb & Gutter (2' Width) (w/ Stone)	\$ 65.00	\$ 1,625.00	\$ 55.50	\$ 1,387.50	\$ 60.00	\$ 1,500.00
23	750	LF	Type A Curb (w/ Stone)	\$ 31.20	\$ 23,400.00	\$ 31.50	\$ 23,625.00	\$ 35.28	\$ 26,460.00
Storm Sewer Improvements									
24	305	LF	12" PVC Storm Drain Pipe	\$ 70.00	\$ 21,350.00	\$ 114.82	\$ 35,020.10	\$ 130.00	\$ 39,650.00
25	32	LF	18" R.C. Pipe, Class 3	\$ 438.00	\$ 14,016.00	\$ 393.89	\$ 12,604.48	\$ 300.00	\$ 9,600.00
26	3	Each	Rebuild / Reset Existing Grate Inlet Top	\$ 4,667.00	\$ 14,001.00	\$ 4,759.38	\$ 14,278.14	\$ 5,800.00	\$ 17,400.00
27	1	Each	Catch Basin Curb Inlet (Double Grate)	\$ 6,100.00	\$ 6,100.00	\$ 14,025.55	\$ 14,025.55	\$ 12,000.00	\$ 12,000.00
28	5	Each	Grate Inlet (Nyloplast Drain Basin)	\$ 3,600.00	\$ 18,000.00	\$ 4,905.75	\$ 24,528.75	\$ 4,747.00	\$ 23,735.00
29	2	Each	Tie to Existing Storm Structure	\$ 2,500.00	\$ 5,000.00	\$ 3,522.30	\$ 7,044.60	\$ 2,500.00	\$ 5,000.00
Erosion Control and Site Maintenance									
30	1	LS	Erosion Control Management and Maintenance	\$ 15,000.00	\$ 15,000.00	\$ 8,185.73	\$ 8,185.73	\$ 50,000.00	\$ 50,000.00
31	350	LF	Sediment Control Logs (Wattle)	\$ 8.00	\$ 2,800.00	\$ 11.17	\$ 3,909.50	\$ 5.00	\$ 1,750.00
32	12	Each	Inlet Protection	\$ 800.00	\$ 9,600.00	\$ 699.08	\$ 8,388.96	\$ 500.00	\$ 6,000.00
Traffic Control, Permanent Signing and Striping									
33	1	LS	Maintenance of Construction Signs and Barricades	\$ 40,000.00	\$ 40,000.00	\$ 25,581.76	\$ 25,581.76	\$ 50,000.00	\$ 50,000.00
34	250	Each	Channelizing Drums	\$ 75.00	\$ 18,750.00	\$ 44.10	\$ 11,025.00	\$ 46.20	\$ 11,550.00
35	850	LF	Yo-docks with Fence Panels	\$ 0.01	\$ 8.50	\$ 39.09	\$ 33,226.50	\$ 32.00	\$ 27,200.00
36	485	LF	Site Constraint Fence	\$ 23.10	\$ 11,203.50	\$ 24.26	\$ 11,766.10	\$ 25.41	\$ 12,323.85
37	4	Each	Portable Sequential Arrow and Chevron Sign Unit	\$ 5,300.00	\$ 21,200.00	\$ 1,470.00	\$ 5,880.00	\$ 1,595.00	\$ 6,380.00
38	4	Each	Portable Changeable Message Signs, Type 2	\$ 10,000.00	\$ 40,000.00	\$ 2,940.00	\$ 11,760.00	\$ 3,135.00	\$ 12,540.00
39	1,140	LF	Solid White, Temporary Traffic Stripe	\$ 0.75	\$ 855.00	\$ 0.79	\$ 900.60	\$ 0.83	\$ 946.20
40	100	LF	Dotted White, Temporary Traffic Stripe	\$ 0.75	\$ 75.00	\$ 0.79	\$ 79.00	\$ 0.83	\$ 83.00
41	1,230	LF	Solid Yellow, Temporary Traffic Stripe	\$ 0.75	\$ 922.50	\$ 0.79	\$ 971.70	\$ 0.83	\$ 1,020.90
42	1,410	SF	Temporary Traffic Control Markings	\$ 2.00	\$ 2,820.00	\$ 2.10	\$ 2,961.00	\$ 2.20	\$ 3,102.00
43	45	SF	Temporary Traffic Control Legends	\$ 2.00	\$ 90.00	\$ 2.10	\$ 94.50	\$ 2.20	\$ 99.00
44	1,140	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)	\$ 2.50	\$ 2,850.00	\$ 2.63	\$ 2,998.20	\$ 2.75	\$ 3,135.00

JDR
Initial

Contractor				Central Alabama Asphalt & Construction Co., LLC		John Plott Company, Inc.		Price Construction Company, Inc.	
45	100	LF	Dotted White, Class 2, Type A Traffic Stripe (5" Wide)	\$ 2.50	\$ 250.00	\$ 2.63	\$ 263.00	\$ 2.75	\$ 275.00
46	1,230	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)	\$ 2.50	\$ 3,075.00	\$ 2.63	\$ 3,234.90	\$ 2.75	\$ 3,382.50
47	1,410	SF	Traffic Control Markings, Class 2, Type A	\$ 8.00	\$ 11,280.00	\$ 8.40	\$ 11,844.00	\$ 8.80	\$ 12,408.00
48	45	SF	Traffic Control Legends, Class 2, Type A	\$ 10.00	\$ 450.00	\$ 10.50	\$ 472.50	\$ 11.00	\$ 495.00
49	1	LS	Relocation of Existing Signs (All Types)	\$ 6,500.00	\$ 6,500.00	\$ 5,040.00	\$ 5,040.00	\$ 12,181.00	\$ 12,181.00
Security Bollard System									
50	1	LS	M30 Rated Active Hydraulically Retractable Bollards (9 Bollards) (Installation Only)	\$ 350,000.00	\$ 350,000.00	\$ 313,668.02	\$ 313,668.02	\$ 310,000.00	\$ 310,000.00
51	1	LS	Remove and Reset Existing Heavy Duty Bollards (Approximately 11 Bollards)	\$ 40,000.00	\$ 40,000.00	\$ 6,352.50	\$ 6,352.50	\$ 6,655.00	\$ 6,655.00
Landscaping Improvements									
52	1,145	SY	Sod	\$ 10.50	\$ 12,022.50	\$ 8.40	\$ 9,618.00	\$ 8.80	\$ 10,076.00
53	1	LS	Remove and Reset Existing Shrubs & Groundcover	\$ 10,000.00	\$ 10,000.00	\$ 4,200.00	\$ 4,200.00	\$ 3,850.00	\$ 3,850.00
54	1	LS	Remove and Reset Chains and Bollards	\$ 15,000.00	\$ 15,000.00	\$ 34,177.50	\$ 34,177.50	\$ 35,800.00	\$ 35,800.00
Miscellaneous Items									
55	1,000	Ton	ALDOT No. 57 Stone (Only as Directed by the Owner's Representative)	\$ 30.00	\$ 30,000.00	\$ 30.35	\$ 30,350.00	\$ 10.00	\$ 10,000.00
56	150	Ton	Utility Trench Foundation Material (ALDOT No. 2 Stone) (Only as Directed by the Owner's Representative)	\$ 32.00	\$ 4,800.00	\$ 41.11	\$ 6,166.50	\$ 40.00	\$ 6,000.00
57	375	SY	Geotextile Separation Fabric (Only as Directed by the Owner's Representative)	\$ 9.33	\$ 3,498.75	\$ 7.93	\$ 2,973.75	\$ 3.00	\$ 1,125.00
58	1	LS	Adjustment of all Valve Boxes, Manhole Ring/Covers, Vaults, Clean-Outs, Meter Boxes, Other Utilities Covers to Finish Grade	\$ 1,500.00	\$ 1,500.00	\$ 6,790.21	\$ 6,790.21	\$ 10,000.00	\$ 10,000.00
59	750	SY	Crushed Stone for Temporary Sidewalks (Only as Directed by the Owner's Representative)	\$ 4.53	\$ 3,397.50	\$ 19.74	\$ 14,805.00	\$ 13.34	\$ 10,005.00
60	1	LS	Geometric Controls	\$ 20,000.00	\$ 20,000.00	\$ 28,925.00	\$ 28,925.00	\$ 9,040.00	\$ 9,040.00
61	1	LS	Record Drawings	\$ 10,000.00	\$ 10,000.00	\$ 5,670.00	\$ 5,670.00	\$ 5,940.00	\$ 5,940.00
62	1	LS	NPDES Stormwater Permitting	Omitted per Addendum 3		Omitted per Addendum 3		Omitted per Addendum 3	
Water System Improvements									
63	60	LF	12" Ductile Iron Waterline, Restrained Joint	\$ 184.00	\$ 11,040.00	\$ 381.82	\$ 22,909.20	\$ 200.00	\$ 12,000.00
64	30	LF	24" Steel Encasement Pipe, Open Cut Installation	\$ 360.00	\$ 10,800.00	\$ 282.23	\$ 8,466.90	\$ 256.00	\$ 7,680.00
65	4	Each	12" 45° Bend	\$ 1,750.00	\$ 7,000.00	\$ 1,254.61	\$ 5,018.44	\$ 1,143.00	\$ 4,572.00
66	2	Each	12" Ductile Iron Sleeve	\$ 2,600.00	\$ 5,200.00	\$ 772.84	\$ 1,545.68	\$ 1,116.00	\$ 2,232.00
TOTAL BASE BID				\$ 1,781,231.31		\$ 2,217,957.79		\$ 1,990,932.45	

I CERTIFY THAT THE ABOVE BIDS WERE RECEIVED SEALED AND WERE PUBLICLY OPENED AND READ ALOUD AT THE TIME AND PLACE INDICATED AND THAT THIS IS A TRUE AND CORRECT TABULATION OF ALL BIDS RECEIVED FOR THIS PROJECT. I RECOMMEND AWARD OF THE CONTRACT FOR CONSTRUCTION TO THE LOWEST RESPONSIBLE AND RESPONSIVE BIDDER AS SHOWN ABOVE, AS DETERMINED BY THE AVAILABLE FUNDS AND SUBJECT TO THE INSTRUCTIONS TO BIDDERS AND ANY APPLICABLE LAW.


Joshua D. Rogers, PE
Thompson Engineering



Sworn to and subscribed before me this 11th day of May, 2023.


Notary Public
My Commission Expires April 4, 2027